

25MIN TURNAROUND

RAMP

(20mins door to door)

BEFORE ARRIVAL:

- CHECK STAND IS CLEAR OF EQUIPMENT & FOD
- RAMP TEAM, BAGS & GROUND EQUIPMENT READY ON STAND (outside ERA)
- MARSHALLER READY, STAND ENTRY GUIDANCE SYSTEM ON (where installed)
- FUELLER / PRM PROVIDER READY

ARRIVAL:

- CHOCKS IN, GPU CONNECTED, CONES AND PIG IN PLACE
- COMPLETE WALK AROUND
- STEPS IN PLACE, IMMEDIATE PAX DISEMBARKATION
- CHECK AND OFFLOAD AFT HOLD FIRST (leave open)
- AMBULIFT READY FOR PRM PAX – USE REAR DOOR (except airbridge stands)
- FUEL TRUCK READY (uplift provided by crew)

ARRIVAL +10:

- INBOUND PAX & BAGS OFF
- CREW COMPLETING CABIN TIDY & SECURITY CHECKS
- PRE-BOARDING PAX TO AIRCRAFT STEPS

ARRIVAL +17:

- LID/eLID WITH CAPTAIN (inform of SI information e.g., EMA, AOG, aft hold empty etc.)

ARRIVAL +20:

- LOADING COMPLETE
- BOARDING COMPLETE, REAR STEPS & PIG REMOVED
- PUSHBACK TUG CONNECTED
- WALKAROUND COMPLETE, CONES REMOVED
- PREPARE FOR PUSHBACK

ARRIVAL +25:

- PUSHBACK

PUSH & HOLD:

- WHERE AIRCRAFT HAS A SLOT DELAY, REQUEST / ANTICIPATE PUSH & HOLD (where permitted)